

PRODUCT CONTROL NOTICE OF ACCEPTANCE

Premdor Entry Systems One Premdor Drive Dickson, TN 37055

BUILDING CODE COMPLIANCE OFFICE

METRO-DADE FLAGLER BUILDING 140 WEST FLAGLER STREET, SUITE 1603 MIAMI, FLORIDA 33130-1563 (305) 375-2901 FAX (305) 375-2908

CONTRACTOR LICENSING SECTION

(305) 375-2527 FAX (305) 375-2558

CONTRACTOR ENFORCEMENT DIVISION

(305) 375-2966 FAX (305) 375-2908

PRODUCT CONTROL DIVISION (305) 375-2902 FAX (305) 372-6339

Your application for Notice of Acceptance (NOA) of:

Castlegate SE Double Door w/sidelites-Outswing -Opaque-8'0" In a Wood Frame

under Chapter 8 of the Code of Miami-Dade County governing the use of Alternate Materials and Types of Construction, and completely described herein, has been recommended for acceptance by the Miami-Dade County Building Code Compliance Office (BCCO) under the conditions specified herein.

This NOA shall not be valid after the expiration date stated below. BCCO reserves the right to secure this product or material at any time from a jobsite or manufacturer's plant for quality control testing. If this product or material fails to perform in the approved manner, BCCO may revoke, modify, or suspend the use of such product or material immediately. BCCO reserves the right to revoke this approval, if it is determined by BCCO that this product or material fails to meet the requirements of the South Florida Building Code.

The expense of such testing will be incurred by the manufacturer.

ACCEPTANCE NO.: 01-1031.03

EXPIRES: 11/05/2006

Raul Rodriguez

Chief Product Control Division

THIS IS THE COVERSHEET, SEE ADDITIONAL PAGES FOR SPECIFIC AND GENERAL **CONDITIONS** BUILDING CODE & PRODUCT REVIEW COMMITTEE

This application for Product Approval has been reviewed by the BCCO and approved by the Building Code and Product Review Committee to be used in Miami-Dade County, Florida under the conditions set forth above.

Francisco J. Quintana, R.A.

Vrancises / accintosa

Director

Miami-Dade County

Building Code Compliance Office

APPROVED: 12/11/2001

Premdor Entry Systems	ACCEPTANCE No.:	01-1031.03

APPROVED: December 11, 2001

EXPIRES: November 5, 2006

NOTICE OF ACCEPTANCE: SPECIFIC CONDITIONS

1. SCOPE

1.1 This renews Notice of Acceptance (NOA) No. 00-0720.07, which was issued on November 9, 2000. It renews the approval of a residential insulated steels door, as described in Section 2 of this NOA, designed to comply with the South Florida Building Code (SFBC), 1994 Edition for Miami-Dade County, for the locations where the pressure requirements, as determined by SFBC Chapter 23, do not exceed the Design Pressure Rating values indicated in the approved drawings.

2. PRODUCT DESCRIPTION

2.1 The Series "Castlegate" Outswing Opaque Double Residential Insulated Steel Door w/Sidelites and its components shall be constructed in strict compliance with the following document: Drawing No 31-1034-CA-O, Sheets 1 through 4 of 4, titled "titled "Premdor (Castlegate Brand) Double Door with Sidelites in Wood Frames with Bumper Threshold-8'0" Height (Outswing)," prepared by manufacturer, dated 6/15/98 and revised on 7/27/01, bearing the Miami-Dade County Product Control renewal stamp with the NOA number and expiration date by the Miami-Dade County Product Control Division. This document shall hereinafter be referred to as the approved drawings.

3. LIMITATIONS

3.1 This approval applies to single unit applications of pair of doors and single door with sidelites, as shown in approved drawings. Single door units shall include all components described in the active leaf of this approval.

4. INSTALLATION

- **4.1** The residential insulated steel door and its components shall be installed in strict compliance with the approved drawings.
- **4.2** Hurricane protection system (shutters):

Door Slab: The installation of this unit will not require a hurricane protective system.

Sidelites: The installation of these units will require a hurricane protective system.

5. LABELING

5.1 Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved".

6. BUILDING PERMIT REQUIREMENTS

- 6.1 Application for building permit shall be accompanied by copies of the following:
 - **6.1.1** This Notice of Acceptance
 - **6.1.2** Duplicate copies of the approved drawings, as identified in Section 2 of this Notice of Acceptance, clearly marked to show the components selected for the proposed installation.
 - **6.1.3** Any other documents required by the Building Official or the South Florida Building Code (SFBC) in order to properly evaluate the installation of this system.

Raul Rodriguez, Chief Product Control Division

APPROVED: December 11, 2001

EXPIRES: November 5, 2006

NOTICE OF ACCEPTANCE: STANDARD CONDITIONS


- 1. Renewal of this Acceptance (approval) shall be considered after a renewal application has been filed and the original submitted documentation, including test supporting data, engineering documents, are no older than eight (8) years.
- **2.** Any and all approved products shall be permanently labeled with the manufacturer's name, city, state, and the following statement: "Miami-Dade County Product Control Approved", or as specifically stated in the specific conditions of this Acceptance.
- 3. Renewals of Acceptance will not be considered if:
 - a) There has been a change in the South Florida Building Code affecting the evaluation of this product and the product is not in compliance with the code changes;
 - b) The product is no longer the same product (identical) as the one originally approved;
 - c) If the Acceptance holder has not complied with all the requirements of this acceptance, including the correct installation of the product;
 - **d)** The engineer who originally prepared, signed and sealed the required documentation initially submitted is no longer practicing the engineering profession.
- **4.** Any revision or change in the materials, use, and/or manufacture of the product or process shall automatically be cause for termination of this Acceptance, unless prior written approval has been requested (through the filing of a revision application with appropriate fee) and granted by this office.
- **5.** Any of the following shall also be grounds for removal of this Acceptance:
 - a) Unsatisfactory performance of this product or process.
 - **b)** Misuse of this Acceptance as an endorsement of any product, for sales, advertising or any other purpose.
- **6.** The Notice of Acceptance number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the Notice of Acceptance is displayed, then it shall be done in its entirety.
- 7. A copy of this Acceptance as well as approved drawings and other documents, where it applies, shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at all time. The engineer need not reseal the copies.
- **8**. Failure to comply with any section of this Acceptance shall be cause for termination and removal of Acceptance.

9. This Notice of Acceptance consists of pages 1, 2 and this last page 3.

END OF THIS ACCEPTANCE

Raul Rodriguez, Chief Product Control Division

PREMDOR (CASTLEGATE BRAND) DOUBLE DOOR WITH SIDELITES IN WOOD FRAMES WITH BUMPER THRESHOLD-8'0" HEIGHT (OUTSWING)




ASTRAGAL

ATTACH ASTRAGAL THROW BOLT STRIKE PLATE TO THE HEADER AND THRESHOLD WITH #10 x 2" FLATHEAD SCREWS

NOTES:


- 1.) WOOD BUCKS BY OTHERS. MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.
 2.) THE PRECEDING DRAWINGS ARE INTENDED TO QUALIFY THE FOLLOWING INSTALLATIONS.
- WOOD FRAME CONSTRUCTION WHERE DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD OPENING.
- B. MASONRY OR CONCRETE CONSTRUCTION WHERE DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY STRUCTURAL WOOD BUCK.
- C. MASONRY OR CONCRETE CONSTRUCTION WHERE DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL ONE BY WOOD BUCK.
- 3. ALL ANCHORING SCREWS TO BE #10 WITH MINIMUM 1 1/2" EMBEDMENT INTO WOOD SUBSTRATE OR 3/16" PFH TAPCONS WITH 1 1/2" MINIMUM EMBEDMENT INTO MASONRY.
- 4. GLAZED UNIT MUST BE INSTALLED WITH "MIAMI-DADE COUNTY APPROVED" SHUTTERS
- 5. THREE STAPLES PER SIDE JAMB INTO HEADER ON SIDELITES AND DOOR, THREE STAPLES PER JAMB INTO THRESHOLD ON SIDELITES AND DOOR.
- 6. LATEX SEALANT TO BE APPLIED AT SIDE BY SIDE JAMBS AND SIDELITES.
- 7. DOOR/SIDELITE HEADER, DOOR/SIDELITE JAMBS, AND SIDELITE BASE CORNERS ARE COPED AND BUTTED.
- 8. DOORS SHALL BE PRE-PAINTED WITH AN ACRYLIC LATEX WATER-BASED/ WATER-REDUCIBLE WHITE PRIMER WITH A DRY FILM THICKNESS OF 0.8 TO 1.2 MIL. 9. FRAMES SHALL BE PRE-PAINTED WITH A WATER-BASED EPDXY PRIMER WITH A DRY FILM THICKNESS OF 0.8 TO 1.2 MIL.





DESIGN PRESSURE RATINGS WHERE WATER INFILTRATION WHERE WATER INFILTRATION REQUIREMENT IS NEEDED * REQUIREMENT IS NOT NEEDED +48.3 psf Positive +48.3 psf

PRODUCT RENEWED


-48.3 psfNegative <u>-48,3 psf</u> ACCEPTANCE No. 01-1031.03 EXPIRATION DATE November 5, 2006 PRODUCT CONTROL DIVISION BUILDING CODE COMPLIANCE OFFICE DADE COUNTY MODIFICATIONS LIMITS: UNLESS NOTED, FRAC. EXTRUSIONS: UNLESS NOTED, STD. COM'L. TOL'S. ADDED PAGE 5 (DOOR OPTIONS)
ADD OTHER DOOR CONFIGURATIONS 10-1-98 RS ENGINEER: REVISIONS DATE BY PART NAME: CASTLEGATE (METAL EDGE) DOUBLE DOOR W/SIDELITES DR. BY R.S. DATE 6-15-98 SCALE: N.T.S. PREMDUR ENTRY SYSTEMS 31-1034-СА-П 911 E. JEFFERSON SHEET 1 OF 6 PITTSBURG, KS. 66762 REVISION LETTER







HER DOOR CONFIGURATIO



EXPIRATION DATE LONG 5, 2006

PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE

DATE 7/30/01

PREMDUR 911 E. JEFFERSON

PITTSBURG, KS. 66762

MAT'L:

31-1034-CA-[]

REVISION LETTER

SHEET 5 OF 6

